

3" HIGH EARTH WATERING BERM

SET TOP OF ROOTBALL 1" ABOVE FINISH GRADE 2-3" LAYER OF GRAVEL, RAKE BACK OVER ROOT BALL AFTER MAINTENANCE PERIOD

BACKFILL MIX, 2 SHOVEL FULLS OF PLANTING MIX PER 5 GAL. (5 SHOVEL FULLS PER 15 GAL.) PLANTING MIXED INTO SOIL. BACKFILL MIX IS NATIVE SOIL FOR AGAVE, CACTUS, AND NATIVE SPECIES. SEE NOTE #14

| SCALE | REVISIONS | | La (Juina) | | DESIGN AND DEVELOPMENT DEPARTMENT | STANDARD PLAN NO. |
|-------------------------|-----------|------|---|-----------|-----------------------------------|----------------------|
| N.T.S. | NO. | DATE | GEM of the DESERT | | DEPARTMENT | |
| Quinto-Carle | | | APPROVED BY: CITY OF LA QUINTA | | SHRUB PLANTING | 703 |
| INCOMPONITION OF THE OF | 1 | | Dujan MM) | 11-4-2020 | DETAIL DATE | SHEET |
| | | | BRYAN McKINNEY PUBLIC WORKS DIRECTOR/CITY ENGINEER R.C.E. NO. 49418 | DATE | | 1 OF 1 |